

## ON-FIELD AUTOMATIC TRACKER INSTALLATION

Enabling the transition from Construction to Manufacturing

Pole insertion

Land removal

Cables positioning

Hyperflex application area

Torque tubes

Transversal beam

Pole raise leveling

Structure bars

Structure bars

#### **APPLICATIONS**

Applications PV Solar plants construcion

#### TARGET MARKETS/CUSTOMERS

Customers

EPC (Engineering, Procurement,
Construction) companies operating
in Solar market; utilities, solar
trackers manufacturers/installers

Outdoor mobile temporary factory for photovoltaic plant manufacturing.


Inside this factory, solar trackers are pre-assembled and then shipped to their final location with a trailer equipped with a custom lifting equipment able to handle this huge structure.

The entire solution is patented by COMAU.

# **HYPERFLEX**

Automatic solar installation





## Scalability

Installation rate is linearly proportional to labour hours: limited availability of human resources in some regions where EPC is committed to install new capacity

### **Health and Safety**

Labour related accidents could slow down or stop solar plants installation resulting in missed production or commissioning delay Health & Safety expenses are predicted to grow linearly proportional to labour hours

#### **Labour Price Inflation**

Labour cost inflation has a direct impact on profitability of overall projects

#### Time to Market

Strong deadline commitment towards customers regarding production start

Resources are not yielding returns while still in construction


### **Competitive Pricing**

Photovoltaic panels cost reduction is flattening; next big cost reduction must come from installation as it is still one of the few sub-optimal areas

## **Price Transparency**

Current improvement in the installation process of Solar farms are unevenly distributed between EPC and Utility companies

## Trolleys with Wheels for Quick Station Relocation



Compatible with Standard Trucks

# Pre-Assembled Robot Station **Referred Components** No Need for Vision Systems Integrated Conveyor System **Elevated Conveyor for Ergonomic Modules Installation** and Trailer Accessibility **Quick Assembly Trolleys**

Up to 25% faster time-to-market for new PV plants Up to 35% savings on the price per panel Up to 30% more modules per hour per operator

#### **Unique Selling Proposition**


**Enhanced Logistics:** tracker components and modules are delivered to the station and the pre-assembled solar blade is then shipped to the final installation position. **Patented Lifting Equipment:** lifting equipment permits accurate positioning of 50m2 solar blade with lifting, pitching and rolling controlled movements

Productivity	60PV Modules/Hrs/Station	
Floor Space	14x38 mq	
HypérFlex Station Reach	660m diameter	
Installation Performance	270 Man-hours/MW	
Availability	24/7	
Tracker Configuration	2P - 1P	
Operators per Shift	17 Operators / 2 Station	
Commissioning	2 shifts / 4,5 operators	

# 2.

## **MINI FLEX**


A compact logistics solution featuring the Hyperflex rover without its dedicated lifting equipment. Mini Flex is a highly efficient mobile system that facilitates the transportation of assembled panels from the production area directly to the field.



Power	Electric		
Autonomy	3 battery slots, up to 8 hours		
Recharge	Possibility for battery replacement		
Weight	8 tons		
Dimensions	L:4600 W:2500 H:1800		
Guidance	1 Operator		
Payload	solar blades up to 1 ton		
Load Bearing Capacity	agricultural soil down to 0.33kg/cm2		
Max Speed	6 km / h with 10% ground slope		
Degrees of freedom	Vehicle Front motion Lateral motion Parallel wheels motion	Carousel Lifting equipment Pitching (+/- 20°) Rolling (+/- 5°) Pushing (200mm)	
Working hours	up to 8 hours with 3 batteries		
Battery specifications	Lead battery, 48V 1620Ah		

# PATENTED LIFTING EQUIPMENT

For solar blade transportation and handling



**Made in Comau**